

Beneficiar: COMUNA MOLDOVITA

Obiectiv: LUCRARI REPARATII POD CU PLATFORMA METALICA IN ZONA CIOCAN, SAT DEMACUSA, COM MOLDOVITA, JUD. SUCEAVA

Obiect: REPARATII POD CU PLATFORMA METALICA

Amplasament: COMUNA MOLDOVITA SAT DEMACUSA

DEVIZ ESTIMATIV LA DATA 25.10.2023

REPARATII POD CU PLATFORMA METALICA

nr. crt.	Simbol articol Denumire articol	U.M.	Cantitate	P.U. a) materiale b) manoperă c) utilaj d) transport	Materiale (3x4a)	Manoperă (3x4b)	Utilaj (3x4c)	Transport (3x4d)	Total (5+6+7+8)
0	1	2	3	4	5	6	7	8	9
1	TSC04G1 Sapatura mecanica cu exc. Pe senile in teren tare imbibat cu apa fundatii culee si deviere curs rau	MC	40,00						
2	TRA01A01 Turnare beton clasa C16/20 in FUNDATIE CULEE POD	mc	25,00						
3	TRA01A01 Turnare beton clasa C35/45 in CULEE POD	mc	7,00						
4	NL Confectionare si montare armaturi diametru 10 mm, 12 mm si diametrul 14 mm fundatie culee	KG	750,00						
5	NL Confectionare si montare armaturi diametru 10 mm, 12 mm si diametrul 14 mm culee	kg	1.450,00						
6	NL Cofraj culee podet	mp	32,00	70					
7	NL CONFECTIONARE SI MONTARE TIMPANE DIN METAL SI BALUSTRADA METALICA	MI	27,00						
8	NL MONTARE PLATFORMA METALICA CFR EXISTENTA LUNGIME	buc	1,00						
9	NL CONFECTIONARE SI ASEZARE ANROCAMENT AMONTE CULEE	mc	180,00						
10	TSC20B1 CONFECTIONARE MONTARE DRENAJ CULEE DIN BOLOVANIS CONCASAT	Mc	40,00						
11	TSC20B1 CONFECTIONARE MONTARE PODINA DIN TABLA METELICA SRRIATA	Mp	28,00						
Total cheltuieli directe									

Total cheltuieli directe

Fd. GARANTAT SALARII 2,25 % + Cheltuieli indirecte 10%

Profit 5%

TOTAL 1

TVA 19%

TOTAL GENERAL (cu rotunjiri)

Intocmit

S.C. SABLUK CONSTRUCT S.R.L.
ING LUPASCU STEFAN

16932900